

Volume Report
Subgrade vs. Stripped

Name	Group	Total	Cut	Area Fill	OnGrade	Volume Cut	Volume Fill	Comp/Ratio Cut	Comp/Ratio Fill	Compact Cut	Compact Fill	Export -Import	Change Per 0.1 ft
Basin	Basin	24,622	14,057	9,613	952	1,510	279	1.00	1.10	1,510	307	1,203	95
Bldg	Bldg	22,807	13,807	7,682	1,318	426	419	1.00	1.10	426	461	-35	87
Grading	Grading	86,945	14,398	68,550	3,997	269	4,393	1.00	1.10	269	4,832	-4,563	347
Regions Total		134,374	42,262	85,845	6,267	2,205	5,091			2,205	5,600	-3,395	529

Stripping Qtys	Group	Plane Area	Slope Area	Depth	Volume
Site Strip	Site	134,374	134,522	0.500	2,491

Sectional Qtys	Group	Plane Area	Slope Area	Depth	Volume
Bldg	Bldg	22,807	22,846	1.000	846
Concrete Pavement	Concrete	21,308	21,308	1.170	923
Grading	Grading	87,809	88,332	0.000	0
Walk	Walk	401	401	0.667	10
Walk	Walk	2,049	2,049	0.667	51
Walk Sub:	Walk	2,450	2,450	0.667	61
Sectional Total		134,374	134,936		1,830

